

AMENDED

6 031366

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241

Operator: Geneva Res. Inc.

Name & Address 50 California St. Suite 930

San Francisco, California 94111

API NUMBER 15-065-00444-00-00

SW NE NW, SEC. 21, T 10 S, R 23 W

2970 ~~4290~~ feet from S section line

4950 feet from E section line

Lease Name Dieboitt Unit Well # 5-1

County Graham Also Known as Brown #1

Well Total Depth 4142 ²⁴ ~~4142~~ RT KCC feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well xx Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Express Well Service License Number 2288 6424

Address Victoria, Ks.

Company to plug at: Hour: PM Day: 23 Month: May Year: 19 90

Plugging proposal received from Gerald Riedel

(company name) Geneva (phone) _____

were: 8 5/8" set at 208' w/175 sks. 5 1/2 set at 4142' w/175 sks.

Stage collar at 1900'. Perfs at 3722 - 3834. Retainer plug at 2616. Perf shot

at 1100'. Order 300 sks 65/35 poz 8% gel 500# bulls. Halliburton Cement Co. Wellbrock.

RECEIVED

JUN 18 2003

KCC WICHITA
(TECHNICAL)

Plugging Proposal Received by _____

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 12:45 PM Day: 23 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Wash down from 1300' - 1600' w/bridge at 1850 open to

1900. Stack out on possible 5 1/2 casing. Part or collapse. Mixed and pumped cement

through tubing. Pump 125 sks to circulation. Lay down 30 joints to 1100'. Mix and pump

75 sks to circ cement. Lay down tubing tie onto 5 1/2 casing. Sq w/total 200 sks. To max

psi 500#. Close in psi 500#. Sq 8 5/8 w/100 sks to max psi 500#. Close in psi 300#.

Remarks: Plug complete.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow