

AMENDED

6-031598

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-03174-00-00
NW
N2 SW ~~34~~ /4 SEC. 21 , 10 S , 23 W
~~900~~ 3630 feet from S section line
4620 feet from E section line

Operator license# 30241 Lease Diebolt LKC Unit well # 5-2
Also Known as Brown A-2

Operator: Geneva Resources, Inc. County Graham

Address: 50 California Street Well total depth 3869 feet
Suite 930 Conductor Pipe: 0 inch @ 0 feet
San Francisco, CA 94111 Surface pipe 8 5/8 Inch @ 215 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

RECEIVED

Company to plug at: Hour: A.M. Day: 15 Month: October 91

JUN 18 2003

Plugging proposal received from: Gerald Riedel

KCC WICHITA

Company: Geneva Resources, Inc. Phone:

Were: 8 5/8" set @ 215' w/175 sx. cwc. 5 1/2" set @ 3848' w/125 sx.
PBTD 3746'. Perf. 3802' - 43'. Casing leaks 1390' - 1525'.
Order 350 sx. 65/35 poz. - 10% gel. - 500# hulls. Allied Cement Co.
Shots @ 1925' - 1100' - 3645'. 5 1/2 open across perfs and taking
fluid.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None ,]

Completed: Hour: 10:45A.M. , Day: 15 , Month: October , Year: 91

Actual plugging report: Squeezed 5 1/2" w/250 sx. cement blend w/400#
hulls mixed in to max. P.S.I. 600#. Close in P.S.I. 300#. Squeezed
8 5/8" w/100 sx. cement blend w/100# hulls to max P.S.I. 400#.
Close in P.S.I. 200#. Plug complete.

Remarks: KB 2370'.

I did / did not observe the plugging. Carl Goodrow

Handwritten initials

(agent)
For [Signature]