

DEC 31 1986

6 030839

API NUMBER 19-065-21,876-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NWNE SEC. 28, T. 10 S. R. 23 W. #

4840 feet from S section line

2200' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6499

Lease Name GEIST Well # 1

Operator: ABRAXES PET. CORP.

County GRAHAM 127.24

Name & Address Box 17485

Well Total Depth 3915' feet

SAN ANTONIO, TEXAS

Conductor Pipe: Size \_\_\_\_\_ feet

78217

Surface Casing: Size 8 5/8 feet 262'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: PM Day: 31 Month: 12 Year: 19 86

Plugging proposal received from VERN

(company name) KELSO CASING (phone) \_\_\_\_\_

were: 8 5/8" SET @ 262' w/ 180 SX 4 1/2" SET @ 3914' w/ 85 SX. TOP PERF. 3656'

ORDER SAND & COM. CNT. SHOOT PIPE & PULL ORDER 200 SX. ATL

65/35 PER 100 12% DICE 1 5 SX. HULLS ALLIED CNT. CO. KELLER WATER

TRUCKS.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2: PM Day: 31 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND FROM 3915 TO 3600 SPOT 4 SX. COM. CNT.

ON SAND WITH DRIER. 1 SHOT @ 2423' RECOVERED 2423' OF 4 1/2"

TIE ON 8 5/8 MIX. & PUMP CNT. MIX & HULLS TO PRESSURE & SQUEEZE

USED 300# HULLS FOLLOWED BY 50 BBL ATL G.M.T. MIX. PRESSURE

TO 1400# MAX. PSI CLOSE IN 1000# PSI USED 100 SX CNT. MIX.

PLUG COMPLETE.

STATE CORPORATION COMMISSION

01-07-87

JAN 7 1987

Remarks: \_\_\_\_\_  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

(If additional description is necessary, use BACK of this form.)  
(did) (did not) observe this plugging.

DATE 1-7-88

Signed Carl Goodrow  
(TECHNICIAN)

INV. NO. 15829