

6 031105

6-2-88

139R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-20,820-0000
SW SE NE, SEC. 27, T 10 S, R 23 W/E
2970 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145

Lease Name Klenk Well # 6

Operator: Dreiling Oil
Name & Address: Box 1000
Victoria, Ks. 67671

County Graham 124.70

Well Total Depth 3837 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 123

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: PM Day: 2 Month: June Year: 19 88

Plugging proposal received from Ivan Edsall

(company name) Dreiling Oil (phone)

were: 8 5/8" set at 123' w/100 sks cwc. 4 1/2" set at 3835' w/150 sks. Perf
3774' - 3786'. Order sand and Common Cement. Pull pipe. Order 200 sks cement
w/5 sks Hulls. Allied Cement Co. Company water trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:00 PM Day: 2 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3720' w/4 sks on sand w/bailer
One shot recovered 1280'. 4 1/2" casing. Squeezed 8 5/8" casing w/200 sks
Cement Blend w/5 sks Hulls mixed into max Psi 700#. Close in Psi 150#.
Plug complete.

RECEIVED STATE CORPORATION COMMISSION

JUN 20 1988

Remarks: (If additional description is necessary, use BACK of this form.)

observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

FORM CP-2/3 Rev. 01-84

INVOICED

DATE 7-13-88

INV. NO. 21313 6-2

AUG 3 1988