

6-2-88

209 R

6 031102

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-20711-0000 1974

SW SW NE, SEC. 27, T 10 S, R 23 W/E  
2970 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145

Lease Name Klenk Well # 2

Operator: Dreiling Oil Inc.  
Name & Address: Box 1000  
Victoria, Ks. 67671

County Graham 124.80  
Well Total Depth 3840 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 152

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement Co. License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: AM Day: 2 Month: June Year: 19 88

Plugging proposal received from Ivan Edsall

(company name) Dreiling Oil (phone) \_\_\_\_\_

were: 8 5/8" set at 152' w/1000 sks cwc. 4 1/2" set at 3839' w/175 sks. PBD 3770'  
Perf 3599' - 3802'. Order sand and Common Cement. Pull pipe. Order 200 sks Cement  
Blend. 5 sks Hulls. Allied Cement Co. Company water trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30AM Day: 2 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3540' w/4 sks Common Cement on sand w/bailer.

2 shots recovered 800' 4 1/2" casing (shot at 1250'). Squeezed 8 5/8" casing w/200 sks  
Cement Blend w/5 sks Hulls mixed into max Psi 500#. Close in Psi 150#. Plug complete.

STATE CORPORATION COMMISSION

JUL 6 1988  
07-06-88

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-12-88

INV. NO. 21273

AUG 3 1988

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow FORM CP-2/3 Rev. 01-84