

351

6 031394

API NUMBER 15-065-21970-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

W/2: NE SE, SEC. 35, T 10 S, R 23 W/E

1980 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5068

Lease Name Schaben Well # 1

Operator: Black Petroleum Co.
Name & Address: Box 12922
Wichita, Ks. 67277

County Graham 127.53

Well Total Depth 3924 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 11 Month: July Year: 19 90

Plugging proposal received from Vernon

(company name) Kelso (phone)

were: 8 5/8 set at 267 w/165 sks. cwc 4 1/2 set at 3922 w/150 sks.

PBTD 3908. Perf 3700-06. Order sand and common cement. Pull pipe.

Order 250 sks 65/35 poz 8% gel, 500 lbs. hulls. Halliburton Cement Co.

Rush Water Trucks. Plugged behind pull so open hole.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30PM Day: 11 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3650 w/4 sks common cement

on sand w/bailer. Recovered 1785 of casing. Sq 8 5/8 w/250 sks cement blend

w/500 lbs. hulls mixed in to max psi 1000 lbs. Close in psi 500 lbs.

Plug complete.

STATE CORPORATION COMMISSION

AUG - 7 1990

Remarks: (if additional description is necessary, use BACK of this form.)

INVOLVED observe this plugging.

DATE: AUG 15 1990

Signed Carl Goodrow (TECHNICIAN)

Gib.S

Carl Goodrow

INV. NO. 28916