

15-065-03045-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
3-13-1968
MAR 13 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Specter Pipe & Supply, Incorporated,

Complete Address: Box #169, Russell, Kansas.

Lease Name Brass field Well No. 2

Location SE-^{NW}NE Sec. 2 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3810

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Company,

Address: Great Bend, Kansas. License No. 457

Operation Completed: Hour 2:00PM Day 9 Month 3 Year 1968

The Above well was plugged as follows:

248'--8 5/8" Surface pipe, cement circulated with 150 Sx.
3801'--4 1/2" Production casing cemented with 100 Sx.

Pushed plug to 3500', sanded well to 3450' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing and squeezed well using 21 sacks gel plus 5 sacks hulls in initial gel and followed with 100 Sx. cement then 9 sacks gel and followed with 20 Sx. cement and finally 5 sacks gel and followed with 10 Sx. cement to bottom of cellar. Maximum pump-in pressure--400#. Final shut-in pressure 250#. (Mudding and cementing operations performed by Allied Cementing Company, Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichol
Well Plugging Supervisor

DATE 3/13/68
INV. NO. 9412-U