

**KANSAS  
STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
3-13-1968  
MAR 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Specter Pipe & Supply, Incorporated,

Complete Address: Box #169, Russell, Kansas.

Lease Name Brown Estate Well No. B-1

Location NE-NE-NW Sec. 2 Twp. 10 Rge. (E) (W)22

County Graham Total Depth 3812'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Company,

Address: Great Bend, Kansas. License No. 457

Operation Completed: Hour 11:15AM Day 9 Month 3 Year 1968

The Above well was plugged as follows:

226'--8 5/8" Surface pipe, cement circulated with 150 Sx.

3809'--5 1/2" Production casing cemented with 150 Sx.

Pushed plug to 3500', sanded well to 3450' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing. Squeezed well using 21 sacks gel plug 5 sacks hulls in initial gel and followed with 100 Sx. cement then 9 sacks gel and followed with 20 Sx. cement and finally 5 sacks gel and followed with 10 Sx. cement to bottom of cellar. Maximum pump-in pressure--500#. Final shut-in pressure 200#. (Mudding and cementing operations performed by Allied Cementing Company, Inc.0.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: M. D. Nichols  
Well Plugging Supervisor

DATE 3/13/68  
INV. NO. 7413-W