


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
APR 23 1967  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Shallow Water Refining Company,

Complete Address: 1325 Wichita Plaza, Wichita, Kansas.

Lease Name Brassfield Well No. 4

Location CN/2-SW-NE Sec. 2 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3790'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling Company,

Address: Box # 405, Chase, Kansas. License No. 346

Operation Completed: Hour 7:30PM Day 31 Month 3 Year 1967

The Above well was plugged as follows:

225'--8 5/8" Surface pipe, cement circulated with 200 Sx.  
3786'--4 1/2" Production casing cemented with 150 Sx. Well plugged back to  
3745'. Top perforations @ 3692'. Well had been squeezed @ 1069' with  
250 Sx. cement.

Sanded well back to 3680' and set 3 Sx. cement with dump bailer..  
Pulled 4 1/2" casing to 600' and circulated heavy gel mud (used 17 Sx. gel).  
Pulled 4 1/2" casing to 540' and displaced 20 Sx. cement thru 4 1/2". Pulled  
4 1/2" to 240' and displaced 20 Sx. cement thru 4 1/2". Pulled 4 1/2", set rock  
bridge @ 30' and 10 Sx. cement to bottom of cellar.  
(Recovered 672' 4 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 4/3/67  
INV. NO. 4989-W