

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Herman George Kaiser,

Complete Address: 909 Palace Building, Tulsa, Oklahoma.

Lease Name Conness Well No. C-2

Location SE-NE-SE Sec. 22 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3870

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pilling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 9

Operation Completed: Hour 12:15PM Day 12 Month 10 Year 1968

The Above well was plugged as follows:

215'--8 5/8" Surface casing cement circulated with 150 Sx.  
3869'--4 1/2" casing cemented on bottom with 150 Sx. Well plugged back to 3730'. Top perforations @ 3712'. DV tool set @ 1780' with 180 Bbl. Chem-Pak.

Sanded well back to 3675' and set 4" Sx. cement with dump bailer. Pulled 4 1/2" casing and squeezed well with initially 16 sacks gel and followed with 100 Sx. cement from 950' to 625' then 11 sacks gel from 625' to 200' and followed with 20 Sx. cement from 200' to 140' then 3 sacks gel from 140' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-400#. Final shut-in pressure-200#. (Cementing and mudding operations performed by Allied Cementing Company, Inc.,).

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

OCT 18 1968

CONSERVATION DIVISION  
Wichita, Kansas

DATE 10/18/68

INV. NO. 8653-W