

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 50-39

LOCATION CNW NE SE

SEC. 22 TWP. 10 RGE. 23

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. K-1 Lease _____ Conness "A"

Operator CO-op Refg Assn Address Box 765 Great Bend, Kans

Field _____ County Graham

Total Depth 3869 Feet.

Plugging Contractor Wilson Inc & 7 Halliburton Co

Plugging Contractor's License No. 375

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 262' circulated with cement - 5 1/2" at 3869' with 75 sax
cement behind - perforated at 3787'

Filled with sand to 3770', set 4 sax cement with dump bailer - pulled
3270' 5 1/2" to 1000', circulated hole with heavy mud at 1000' (63 sax GeL)

displaced 20 sax cement through 5 1/2" at 700' - heavy mud to 250', set
20 sax cement at 250' - heavy mud to 35', cement 35' to 0'

Cementing and mudding by Halliburton Co.

Edwin Petty
District Conservation Agent

Date 11-21-57

RECEIVED
STATE CORPORATION COMMISSION

NOV 25 1957
11-25-57
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 22 T 10 R 23 W
BOOK PAGE 50 OF 39