

15-005-20733-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 8 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil Inc.

Complete Address RR 2 Victoria Ks.

Lease Name Klenk Well No. 3

Location C-N/2-SW-NE Sec. 27 Twp. 10 Rge. 23 (W) (W)

County Graham Total Depth 3826

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Dreiling Oil Inc.

Address RR 2 Victoria Ks. License No. _____

Operation Completed: Hour 3:00 AM Day 7 Month 1 Year 1975

The above well was plugged as follows:

K.B. 2321 - Dakota Top + 1600 -

112' of 8 5/8" cwc 100 SX

70 SX cement 50/50 permix 6% gel @ 900'

20 " " " " " " @ 120'

12 SX Hulls push wooden plug to 40'

10 SX cement 50/50 permix 6% gel on top.

I hereby certify that the above well was plugged as herein stated.

Signed: Walter Batthazor
Well Plugging Supervisor

INVOICED

DATE 1/9/75

INV. NO. 615-W