

15-065-20727-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil Inc.
 Complete Address Route 2 Victoria Ks.
 Lease Name Geist Well No. 3
 Location SE-SE-NW Sec. 27 Twp. 10 Rge. 23 (X) (W)
 County Graham Total Depth 3845
 Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
 Other well as hereafter indicated _____
 Plugging Contractor Dreiling Oil Inc.
 Address Route 2 Victoria Ks. License No. 730
 Operation Completed: Hour 5:00 PM Day 13 Month 1 Year 1975

The above well was plugged as follows:

K.B. Elev 2309 Dakota Top. 1625 138' of 8 5/8" cwc 125 SX
 4 1/2" csg. @ 3843 cw 100 SX Recovered. 3395'
 perf. 3688. set plug @ 3600' dumped 50' of
 sand & 4 SX cement on top of plug. Pumped down 8 5/8"
 4 SX Halls - 14 SX Gel - 70 SX cement 50/50
 poz mix 6% Gel - 11 SX Gel - Released plug
 30 SX cement 50/50 poz mix 6% Gel.
 100# closing pressure. sun cementing.

I hereby certify that the above well was plugged as herein stated.

Signed: Nate F. Battherson
Well Plugging Supervisor

INVOICED

DATE 1/15/75
INV. NO. 644W