

15-065-03222-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 29-18

LOCATION NE SE NW

SEC. 33 TWP. 10 RGE. 23

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Walker

Operator Gulf Oil Co Address Box 2233 Wichita, Kans

Field _____ County Graham

Total Depth 3850 Feet.

Plugging Contractor Morgan Pipe Pulling

Plugging Contractor's License No. 43

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 267' circulated with cement - 5 1/2" 3848' with 100 sax cement

behind - Cement to 3810', perforated 3615',

Filled with sand to 3600', set 4 sax cement with dump bailer, pulled

3060' 5 1/2" - hole filled with Kem-Pac and chunk mud to 260', set rock

and 20 sax cement, heavy chunk mud to 35', set rock and 10 sax cement

to bottom cellar.

District Conservation Agent

Date 8-10-57

PLUGGING
FILE SEC 33 T 10 R 23W
BOOK PAGE 29 LINE 18

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1957

CONSERVATION DIVISION
Wichita, Kansas