

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 29-15

LOCATION NE NE NW

SEC. 33 TWP. 10 RGE. 23

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Walker

Operator Gulf Oil Co Address Box 2233 Wichita, Kans

Field _____ County Graham

Total Depth 4096 Feet.

Plugging Contractor Morgan Pipe Pulling Co

Plugging Contractor's License No. 43

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 257' circulated with cement - 5 1/2" at ~~3210~~ 3901' with

175 sax cement behind and circulated to 0' with Kem Pac -

P.B. 3865' perforated 3772'.

Filled with chat to 3760', set 4 sax cement with dump bailer, pulled

5 1/2" - filled with heavy mud to 257', set rock and 20 sax cement,

heavy mud to 35', set rock and 10 sax cement to bottom cellar.

Edna Lester
District Conservation Agent

Date 8-5-57

RECEIVED
STATE CORP. COMMISSION
AUG 10 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 33 T. 10 R. 23W
BOOK PAGE 29 LINE 15