


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 1 Twp. 10 Rge. 24 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner D. G. Hansen
Lease Name George Gano Well No. 1
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 15 1961
Application for plugging filed June 15 1961
Application for plugging approved June 15 1961
Plugging commenced June 15 1961
Plugging completed June 15 1961
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4045 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210.59'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 400'. Set plug. Put in 20 sacks cement. Filled to 200'. Set plug. Put in 20 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway 107 Rule Building
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of June, 1961

Vicky Jacobs
Vicky Jacobs Notary Public.

My commission expires May 20, 1963



15-065-02065-0000

WELL LOG

OPERATOR D. G. Hansen **SEC.** 1-10-24W
WELL NAME George Gano #1 **LOC.** NE NE NE
TOTAL DEPTH 4045' **COUNTY** Graham
COMM. June 5, 1961 **COMP.** June 15, 1961 **STATE** Kansas
RIG NO. 1- **ELEVATION** 2466' R. B.

CASING: Ran 210.59' (10 jts.) 8-5/8" OD Surface Casing. **PRODUCTION:** D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	210	Shale		
210	1285	Sand & Shale		
1285	1595	Shale		
1595	1780	Sand		
1780	1905	Shale		
1905	2085	Red Bed		
2085	2120	Anhydrite		
2120	2250	Shell & Shale		
2250	2895	Shale & Lime	0° - 2500	
2895	2935	Lime	0° - 2750	
2935	3080	Lime & Shale	0° - 3000	
3080	3200	Shale & Lime		
3200	3290	Lime & Shale	0° - 3250	
3290	3550	Shale & Lime	0° - 3500	
3550	3715	Lime & Shale		
3715	3810	Shale & Lime	0° - 3750	
3810	3870	Lime		
3870	3908	Lime & Shale		
3908	3974	Lime		DST 3956-3974'
3974	3994	Lime & Shale		DST 3971-3994'
3994	4004	Lime	0° - 4000	
4004	4045	Lime & Shale		

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 21 1961
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By

G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 20th day of June, 1961.

My commission expires:
May 20, 1963

Vicky Jacobs - Notary public

