

WELL PLUGGING RECORD

	■	■	
	■	■	

Graham County. Sec. 1 Twp. 10 Rge. 24 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines. NE NE SE

Lease Owner D. G. Hansen

Lease Name George Gano "C" Well No. 1

Office Address Logan, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 17 19 64

Application for plugging filed April 17 19 64

Application for plugging approved April 17 19 64

Plugging commenced April 17 19 64

Plugging completed April 17 19 64

Reason for abandonment of well or producing formation To low structually

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Filled hole with heavy mud to 540'. Set plug. Put in 20 sacks cement. Filled with heavy mud to 180'. Set Plug. Put in 20 sacks cement & 1/2 sack hulls. Filled with heavy mud up to 40'. Set plug. Filled to top with 10 sacks cement & 1/2 sack hulls.

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1966

CONSERVATION DIVISION 04-27-64
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G DRILLING CO.

Address 107 Rule Building, Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Jay H. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway
107 Rule Building
 (Address)

(Address)

SUBSCRIBED AND SWORN to before me this 20th day of April, 19 64
 My commission expires May 20, 1967
Vicky Jacobs
 Vicky Jacobs

_____, 19____
Vicky Jacobs
 Vicky Jacobs _____
 Notary Public.



15-065-02068-0000

WELL LOG

OPERATOR D. G. Hansen
 WELL NAME George Gano "C" #1
 TOTAL DEPTH 4020'
 COMM. 4/7/64 COMP. 4/17/64
 RIG NO. 1
 CASING: Set 188.26' (10 jts.) 8-5/8" OD Surface Casing.
 SEC. 1-10-24W
 LOC. NE NE SE
 COUNTY Graham
 STATE Kansas
 ELEVATION 2450' K.B.
 PRODUCTION: D&A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	645	Shale	500' - 1/2°	
645	1305	Shale & Sand	1000' - 1/2°	
1305	1360	Shale		
1360	1450	Sand		
1450	1620	Shale & Red Bed	1500' - 1/4°	
1620	1810	Sand		
1810	2066	Shale & Red Bed	2000' - 1/2°	
2066	2100	Anhydrite		
2100	2285	Shale & Shells		
2285	2900	Shale & Lime	2500' - 1/4°	
2900	3020	Lime	3000' - 3/4°	
3020	3595	Lime & Shale		
3595	4020	Lime		

DST 3935-3952'
 DST 3951-3972'
 DST 3970-3992'

RECEIVED
 STATE CORPORATION COMMISSION

APR 27 1964

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway
 Jay H. Galloway

THIS 20th day of April, 1964.

Vicky Jacobs
 Vicky Jacobs - Notary Public

