

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_

LEASE NAME Diebolt LKC Unit

WELL NUMBER 3-4

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4290 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR Geneva Resources, Inc.

SEC. 20 TWP. 10 RGE. 23 (K) or (W)

ADDRESS 50 California St., Ste. 930, San Francisco, CA 94111 COUNTY Graham

PHONE#(415) 291-9500 OPERATORS LICENSE NO. 30241 Date Well Completed 12/23/55

Character of Well Input Plugging Commenced 2/15/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 2/15/90

The plugging proposal was approved on 2/15/90 (date)

by Don Butcher and Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? Yes

Producing Formation LKC Depth to Top 3711' Bottom 3907' T.D. 3907'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation  | Content    | From Surf.   | To          | Size          | Put In       | Pulled out  |
|------------|------------|--------------|-------------|---------------|--------------|-------------|
| <u>LKC</u> | <u>Oil</u> | <u>Surf.</u> | <u>224'</u> | <u>8-5/8"</u> | <u>224'</u>  | <u>None</u> |
|            |            | <u>Surf.</u> | <u>3907</u> | <u>5-1/2"</u> | <u>3907"</u> | <u>None</u> |
|            |            |              |             |               |              |             |
|            |            |              |             |               |              |             |
|            |            |              |             |               |              |             |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated the base of the Dakota at 1100' and the base of the Anhydrite at 1925'. Spotted 50 sacks of Class A cement at 1995'. Pull up hole to approximately 1600' and pump and circulate cement to surface. Removed no casing from the wellbore.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address P. O. Box 428, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Geneva Resources, Inc.

STATE OF California COUNTY OF San Francisco, ss.

Thomas G. Smith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas G. Smith


(Address) 50 California St., Ste. 930, San Francisco CA 94111

STATE CORPORATION COMMISSION  
MAR 30 1990

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 1990

Wichita, Kansas

Jacquelyn Wishom  
Notary Public



Expires: 2-8-91