

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_

LEASE NAME Diebolt LKC Unit

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 4-3

4290 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 20 TWP. 10 RGE. 23 (X) or (W)

COUNTY Graham

LEASE OPERATOR Geneva Resources, Inc.  
50 California Street, Suite 930  
ADDRESS San Francisco, CA 94111

PHONE# (415) 291-9500 OPERATORS LICENSE NO. 30241

Date Well Completed 7/10/54

Character of Well Oil

Plugging Commenced 10/17/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/17/90

The plugging proposal was approved on October 17, 1990 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? No/Unavailable

Producing Formation LKC Depth to Top 3652' Bottom N/A T.D. 3915'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surf.	245	10-3/4"	245'	None
LKC	Oil	Surf.	3886	7"	3886'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated the Base of the Dakota at 1100' and the Base of the Anhydrite at 1925'. Ran tbg to 2000' and pumped 100 sx of cement. Pulled up hole to 1000' and pumped 100 sx of cement. Circulated. Maximum pressure of 500 psi and closed in at 500 psi. Pumped down 10-3/4" surface csq with 100 sx of cement at a maximum pressure of 300 psi and closed in at 300 psi.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hallibuton Services License No. 5287

Address P. O. Box 428, Hays, KS 67672

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Geneva Resources, Inc.

STATE OF California COUNTY OF San Francisco, ss.

Thomas G. Smith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 5 1990

(Signature) Thomas G. Smith  
(Address) 50 California Street, Suite 930  
San Francisco, CA 94111

SUBSCRIBED AND SWORN TO before me this 2<sup>ND</sup> day of November, 19 90  
Wichita, Kansas

Jacquelyn Wishom  
Notary Public

Commission Expires: 2-8-91

