

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 20 Twp. 10S Rge. 23W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE NE SW

Lease Owner Petroleum Management, Inc.

Lease Name Walker Well No. 1

Office Address 1515 Wichita Plaza Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed November 15 1967

Application for plugging filed November 15 1967

Application for plugging approved November 15 1967


Plugging commenced November 15 1967

Plugging completed November 15 1967

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W.L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3920 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	208'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole, @1010' w/100
sx cem, Plug @240' w/20 sx
cem, Top plug @40' w/10 sx
cem, to bottom off cellar.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Maxine V. Starr

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Starr

(Address) _____, 19 67

SUBSCRIBED AND SWORN to before me this 20th day of November

Betty M. Maloney Notary Public.

My commission expires _____



DRILLERS LOG

Walker No. 1

CASING RECORD: 8 5/8" @ 208' w/150 sx cement
 COMPANY: Petroleum Management, Inc.
 CONTRACTOR: Red Tiger Drilling Co.
 COMMENCED: November 7, 1967
 COMPLETED: November 15, 1967
 TOTAL DEPTH: 3920
 DESCRIPTION: SE NE SW 20-108-23W Graham Co., Ks.
 ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay Sand	0	40	
Shale	40	1220	
Sand	1220	1280	
Shale	1280	1305	
Shale, Shell, Red Bed	1305	1645	
Shale & Shells	1645	1935	
Anhydrite	1935	1975	
Shale & Shells	1975	2135	
Shale w/Lime	2135	3565	
Lime	3565	3920	

RECEIVED
 STATE CORPORATION COMMISSION
 11-22-1967
 NOV 22 1967
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Starr
 Maxine V. Starr

Subscribed and sworn to before me this 20th day of November, 1967.

Betty M. Maloney
 Betty M. Maloney
 Notary Public

My Commission Expires:

3-22-71

