


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 6 Twp. 10 Rge. 24 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines C SE SE
Lease Owner Empire Drilling Co.
Lease Name Reidel Well No. D-1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 3-31-62 19__
Application for plugging filed 19__
Application for plugging approved 8-13-68 19__
Plugging commenced Aug. 1 19 68
Plugging completed Aug. 6 19 68
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4055 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4055 feet to surface feet for each plug set.
Sanded up to 3840' dump 5 sacks of cement on bottom. Pulled pipe from hole pump 5 huls 30 sacks of mud 100 sacks of cement in hole. Well completed.

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.
Address P.O. Box 313 Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Dan J. Kornfeld
(Address) _____



SUBSCRIBED AND SWORN to before me this 29th day of August, 19 68
October 21, 1970
Lucille H. Harr
Notary Public.

LOG

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Riedel "D" # 1
 LOCATION: C SE SE of Section 6-10S-24W, Graham County, Kansas
 COMMENCED: March 19, 1962 ELEVATION: 2511 KB
 COMPLETED: March 31, 1962 POTENTIAL:

0	to	160	Shale
160	to	1430	Shale-Shells
1430	to	2000	Shale-Sand-Shells
2000	to	2151	Shale
2151	to	2188	Anhydrite
2188	to	2235	Shale
2235	to	2685	Shale-Shells
2685	to	2820	Shale-Lime
2820	to	2890	Shale-Shells
2890	to	3440	Shale-Lime
3440	to	3515	Broken Lime
3515	to	3615	Shale w/Lime Streaks
3615	to	3785	Shale-Lime
3785	to	3860	Lime
3860	to	3865	Lime-Chert
3865	to	4015	Lime
4015	to	4055	Lime-Shale
4055			Rotary Total Depth

SET: 148' of 8 5/8" casing with 75 sacks cement.
 3958' of 5 1/2" casing with 100 sacks cement.

ELECTRIC LOG TOPS:

Heebner	3789	-1278
Toronto	3812	-1301
Lansing	3823	-1312
Log Total Depth	4057	

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 4 1968
 CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Riedel "D" # 1, C SE SE of Section 6-10S-24W, Graham County, Kansas, as reflected by the files of Empire Drilling Company.

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 8th day of April, 1962.

Lucille H. Harr
 Lucille H. Harr, Notary Public

My commission expires October 21, 1962.