


15-065-01034-0000
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

GRAHAM County. Sec. 06 Twp. 10S Rge. 24 (XXXXX)(W)

Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner EMPIRE DRILLING COMPANY
Lease Name Riedel F Well No. 1
Office Address 650 FOURTH NATIONAL BANK BLDG, WICHITA 2, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 20 19 62
Application for plugging filed October 20 19 62
Application for plugging approved October 20 19 62
Plugging commenced October 20 19 62
Plugging completed October 20 19 62
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation Depth to top Bottom Total Depth of Well 4030 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Hole	0	160	8 5/8"	124'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug set at 540' with 20 sacks.
Plug set at 150' with 20 sacks.
Plug set at 35' with 10 sacks.

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1962 10-30-62

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY
Address 650 FOURTH NATIONAL BANK BLDG, WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
650 FOURTH NATIONAL BANK BLDG, WICHITA 2, KANSAS
(Address)

Subscribed and sworn to before me this 29th day of October, 1962

My commission expires

Oct 21, 1966

Lucille H. Harr
Notary Public.



15-065-01034-0000

LOG

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Riedel F #1
 LOCATION: C NE SW Section 6-10S-24W, Graham County, Kansas
 COMMENCED: October 10, 1962 ELEVATION: 2485 KB
 COMPLETED: October 20, 1962 POTENTIAL: D & A

 0 to 160 Surface Hole
 160 to 1575 Shale
 1575 to 2130 Shale & Sand
 2130 to 2167 Anhydrite
 2167 to 2835 Shale & Shells
 2835 to 3775 Lime & Shale
 3775 to 3805 Lime-Chert
 3805 to 4030 Lime
 4030 RTD

SET: 124' of 8 5/8" with 75 sacks cement.


SCHLUMBERGER LOG TOPS:

Heebner	3758	-1273
Toronto	3781	-1296
Lansing Kansas City	3794	-1309
Base Kansas City	4025	-1540
Log Total Depth	4029	

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 30 1962
 CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Riedel F #1, C NE SW Section 6-10S-24W, Graham County, Kansas, as reflected by the files of Empire Drilling Company.



Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 29th day of October, 1962.

Lucille H. Harr
 Lucille H. Harr, Notary Public

My commission expires October 21, 1966.