

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 4 Twp. 10S Rge. (E) 24 (W)

Location as "NE/CNW/SW" or footage from lines. NE NE NE

Lease Owner Murfin-Rains & Williamson

Lease Name Critchfield Well No. 1

Office Address 617 Union Center, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-29 19 57

Application for plugging filed 10-29 19 57

Application for plugging approved 10-29 19 57

Plugging commenced 10-29 19 57

Plugging completed 10-29 19 57

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Box 326, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4555 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	203'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First plug at 750' mixed and displaced 20 sacks through drill pipe. Set second plug at 190' mixed 20 sacks and displaced through drill pipe. Set third plug at 40' mixed 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company

Address 617 Union Center, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

W. R. Murfin (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) WR Murfin

(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of November, 19 57

My commission expires June 14, 1961

Phyllis Brown
Phyllis Brown Notary Public.



11-14-1957
RECEIVED

DIVISION
NSAS

PLUGGING
FILE SEC 4 T. 10 R. 24W
BOOK PAGE 58 LINE 27

15-065-00988-00-00

WELL LOG

COMPANY **Murfin Drilling Co.**

SEC. 4 T. 10S R. 24W


FARM **Critchfield** NO. 1

LOC. NE NE NE

TOTAL DEPTH **4555'**
COMM. **10-15-57**

COMP. **10-29-57**

COUNTY **Graham**
KANBAS



SHOT OR TREATED
CONTRACTOR **Murfin Drilling Co.**
ISSUED

CASING

20	10
15	8 5/8" @ 203' w/150 SXS.
12	6
13	5

ELEVATION **2474 KB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

TOPS:

203	Cement	Heebner	3778
490	Shells - Shale	Toronto	3802
570	Sand	Lansing-Kansas City	3818
1105	Shale - Shells	Base Kansas City	4045
1240	Sand	Ft. Scott	4167
1400	Shale - Shells	Cherokee	4218
1685	Shale - Shells - Red Bed	Mississippi Chert	4346
1865	Sand	Mississippi Lime	4378
1900	Red Bed - Shale	Gilmore City	4412
2120	Shale	Kinderhook Shale	4446
2160	Anhydrite	Viola	4467
2470	Shale	Simpson	4522
2600	Shale - Shells	Arbuckle	4530
3770	Lime - Shale	RTD	4555
4210	Lime		
4270	Lime - Shale		
4345	Lime		
4380	Chert		
4416	Miss Lime		
4447	Lime		
4467	Shale - Dolomite		
4528	Dolomite		
4538	Shale - Dolomite		
4555	Dolomite		

PLUCCING
FILE SEC 4 T 10 R 24W
BOOK PAGE 58 LINE 27

RECORDED
NOV 14 1957

State of Kansas }
County of Sedgwick } SS:

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Critchfield # 1 well.

W R Murfin

Subscribed and sworn to before me this 7th day of November 19 57

My Commission Expires June 14, 1961

Phyllis Brown
Phyllis Brown NOTARY PUBLIC

