

API NUMBER 15-065-20,791

LEASE NAME Geo. Nickelson B

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 6

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 4 TWP. 10 RGE. 24 (E) or (W)

COUNTY Graham

Date Well Completed 10-30-75

Plugging Commenced 6-26-86

Plugging Completed 7-2-86

LEASE OPERATOR Don E. Pratt

ADDRESS P.O. Box 370 - Hays, KS 67601

PHONE# (913) 625-3446 OPERATORS' LICENSE NO. 6114

Character of Well Murfin Drlg.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? KCC

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.D. 4130'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Csg.	0	225'	8 5/8"	225'	None
	Casing	0	4110	4 1/2"	4110'	1350'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3930', dumped 5 sxs cement on top of sand, pulled 1350' 4 1/2" casing and plugged to surface with 200 sxs Econolite & 5 sxs Hulls

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No.

Address East 8th St. - Hays, KS 67601

STATE OF Kansas COUNTY OF Ellis, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Don E. Pratt

(Address) P.O. Box 370 - Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 18th day of July, 19 86

RECEIVED
 STATE CORPORATION COMMISSION
 CONS. DIV. WICHITA, KS
 Notary Public Helen Ubert

My Commission Expires

Helen Ubert
 NOTARY PUBLIC
 State of Kansas
 My Annot. Expires July 22, 1989

7-21-1986
 [JUL 21 1986]


WELL LOG

COMPANY Don E. Pratt
FARM NICKELSON "B" NO. 6

SEC. 4 T. 10S R. 24W
LOC. NE SW NW

RID. NO. 16
TOTAL DEPTH 4130'
COMM. 10/23/75 COMP. 10/30/75

COUNTY Graham
KANSAS



CONTRACTOR Murfin Drilling

CASING
10 5/8" @ 225' w/150 SX
15
12 6
13 5
4 1/2" @ 4110' w/150 SX

ELEVATION
PRODUCTION Producer

FIGURES INDICATE BOTTOM OF FORMATIONS

- 175 - surf soil & sand w/lime stone
- 225 - shale (blue)
- 1415 - shale, sand
- 1710 - shale
- 1915 - sand (cedar hill)
- 2050 - shale (red bed)
- 2164 - shale
- 2198 - anhydrite
- 2515 - shale
- 3925 - lime, shale
- 4090 - lime
- 4130 - lime, shale
- 4130 - TD

State of Kansas
County of Sedgwick

I, James R. Daniels of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the George Nickelson "B" #6 well.



Subscribed and sworn to before me this 5th day of November 19 75

James R. Daniels

JOLENE S. FRISBIE, STATE NOTARY PUBLIC
My Commission Expires: My Comm. Exp. March 13, 1979

Jolene S. Frisbie
NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION
6-3-1986
JUN 03 1986
CONSERVATION DIVISION
Wichita, Kansas