

15-065-01750-00-00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
4-1-1968  
APR 1 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Skelly Oil Company,

Complete Address: 1860 Lincoln Street, Denver, Colorado.

Lease Name C. R. Acheson Well No. 1

Location SW-SW-SE Sec. 14 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3749

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 2:00 PM Day 27 Month 3 Year 1968

The Above well was plugged as follows:

297'--8 5/8" Surface pipe, cement circulated with 150 Sx.

3741'--5 1/2" Production casing cemented on bottom with 250 Sx. Open hole completion.

Dakota leak squeezed @ 1134' with 200 Sx. cement.

Checked fluid level in well, found fluid @ 2650'. Ran 6 yards Redi-Mix cement.

checked top of cement @ 1450'. Ran another 8 yards Redi-Mix cement to fill hole to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/1/68

INV. NO. 4507-W

Signed: [Signature]  
Well Plugging Supervisor