

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
3-16-1970  
MAR 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Birmingham-Bartlett Drilling Company,

Complete Address 300 Kaufman Building, Wichita, Kansas.

Lease Name Mincks Well No. 2

Location NW-SW-NE Sec. 25 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3727'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Sun Oil Well Cementing, Incorporated,

Address Box #69, Hays, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 1:00 PM Day 9 Month 3 Year 1970

The above well was plugged as follows:

158'--8 5/8" Surface casing, cement circulated.  
3723'--5 1/2" Production casing, cemented on bottom with 125 Sx. Well has been squeezed  
in Dakota to surface with 200 Sx. cement. Checked fluid level in well & found fluid  
@ 125'.

Attempted to run tubing to bottom of well. Was unable to get tubing below 2890'.

Displaced 10 Sx. cement thru Tubing @ 2890'. Pulled tubing to 2700' and circulated

heavy gel mud using 26 sacks gel. Pulled tubing to 800' and displaced 50 Sx. cement

thru tubing from 800' to 400' Pulled tubing to 400' and pumped in 4 sacks gel to

circulate gel again Pulled tubing and filled 5 1/2" to bottom of cellar with 5 Sx. cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichole  
Well Plugging Supervisor

DATE 3/17/70

INV. NO. 1593-4