

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6-15-1964
JUN 15 1964

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Union Texas Petroleum,

Complete Address: Drawer "D", Great Bend, Kansas.

Lease Name Herrold Well No. 5

Location NW*NW-NW Sec. 25 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3748

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Incorporated,

Address: Box # 221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 2:30PM Day 10 Month 6 Year 1964

The Above well, was plugged as follows:

205'--8 5/8" Surface pipe, cement circulated. 3742'--5 1/2" production casing set and cemented.
Sanded well back to 3730' and set 4 Sx. cement with dump bailer. Pulled 5 1/2" to 600' and attempted to circulate heavy gel mud, pumped in 10 Sx. gel but failed to get circulation. Pulled 5 1/2" to 510' and pumped in 5 Sx. gel but still could not gain circulation, displaced 20 Sx. cement thru 5 1/2" @ 510'. Pulled 5 1/2" to 190', circulated heavy gel mud and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge @ 35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. D. Nichols
Well Plugging Supervisor

DATE 6/15/64
INV. NO. 9303-W