

~~KANSAS~~

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
11-25-1974
NOV 25 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sun Oil Company,
Complete Address 800 Security Life Building, Denver, Colorado.
Lease Name Diebolt-L-KC Well No. Tract-12, Well #4
Location SE-SW-NE Sec. 28 Twp. 10 Rge. (E) (W) 23
County Graham Total Depth 3911'
Abandoned Oil Well Gas Well Input Well X SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Charlie Crow Drilling Company,
Address P. O. Box #706, Hays, Kansas License No. 733
Operation Completed: Hour 2:30 PM Day 20 Month 11 Year 1974

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated.
3706'--5 1/2" casing cemented on bottom with an unknown quantity. 5 1/2" has been squeezed
@ 3242' with 50 Sx. cement, @1306' with 100 Sx. cement and @1017' with 50 Sx. cement.
Well plugged back to 3875'. Perforations from 3625' to 3826'.

Pushed plug to 3600', sanded back to 3575' and set 4 Sx. cement with dump bailer.

Pulled 5 1/2" casing (730') and squeezed well initially with 5 sacks hulls and 11 sacks
gel following with 110 Cu. Ft. cement from 1000' to 675' then 11 sacks gel from 675'
to 235' and followed with 30 Cu. Ft. cement from 235' to 160' then 3 sacks gel from

160' to 40' and finally 10 Cu. Ft. cement from 40' to base of cellar. Max. Pump-in
pressure-400#. FSIP-200#. (Mudding and cementing by Allied Cementing Co. Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 11/25/74

INV. NO. 363-W