

KANSAS

Form CP-3
Rev. 6-4-68STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION
11-15-1974
NOV 15 1974
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sun Oil Company,

Complete Address 800 Security Life Building, Wichita, Kansas.

Lease Name Diebolt-L-KC Well No. Tract-15, Well #2

Location NW-NE-SE Sec. 28 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3900'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Charlie Crow Drilling Company,

Address Box #706, Hays, Kansas. License No. 733

Operation Completed: Hour 1:30 PM Day 8 Month 11 Year 1974

The above well was plugged as follows:

398'--9 5/8" Surface casing, cement circulated with 250 Sx.

3899'--5 1/2" casing cemented on bottom with 200 Sx. Well plugged back to 3824'. Per-

forations from 3781' to 3823'.

Sanded well back to 3775' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing

(2505') and squeezed well initially with 5 sacks hulls and 13 sacks gel following with

110 Cu. Ft. cement from 1000' to 675' then 6 sacks gel from 675' to 435' and followed

with 35 Cu. Ft. cement from 435' to 360' then 11 sacks gel from 360' to 40' and finally

15 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure-1000#.

FSIP-250#. (Mudding & cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging SupervisorDATE 11/15/74
INV. NO. 299-W