

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION CS 1/2 NW NE

SEC. 28 TWP. 10 RGE. 23

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 3-A Lease Wickizer

Operator W. E. Wickizer Address Wakeeney, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3865 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 208' circulated with cement - 5 1/2" 3863 with 100 sax  
cement behind - perforated 3640'.

Filled with sand to 3630', set 5 sax cement with dump bailer,  
pulled 2705' 5 1/2" to 1000', circulated hole with heavy mud (25 sax Gel),  
pulled 5 1/2" - filled hole with heavy mud to 208', set rock and  
20 sax cement, heavy chunk mud to 35', set rock and 10 sax cement  
to bottom cellar.

*Edna Perry*  
District Conservation Agent

Date 8-19-57

PLUGGING  
FILE SEC. 28 T. 10 R. 23W  
BOOK PAGE 39 LINE 7

RECEIVED  
STATE CORPORATION COMMISSION  
8-20-1957  
AUG 20 1957  
CONSERVATION DIVISION  
Wichita, Kansas