

15-065-01786-00-00
6 070833

4-11-90

168 P

API NUMBER 15- 11-1-61

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION C N/2 NE SW, SEC. 25, T 10 S, R 21 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Operator: Kaiser Francis Oil Co.
Name & Address: Box 21468
Tulsa, Ok. 74121-1468
Glenn Jackson

_____ feet from S section line

_____ feet from E section line

Lease Name White Well # 6

County Graham Co. 120.80

Well Total Depth 3717 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan Baker's Well Service License Number _____

Address Hays, Ks. Codell, Ks.

Company to plug at: Hour: AM Day: 11 Month: April Year: 19 90

Plugging proposal received from John Hatcher

(company name) Kaiser Francis Oil Co. (phone) _____

were: 8 5/8" 207' cwc w/125 sks. 5 1/2" casing set at 3713' w/125 sks cement.

C.I.B.P. at 3615' d.v. tool at 1612' cwc w/375 sks cement. Peffs at 3713-17 O.H.

Proposal 325 sks 65/35 poz 8% gel and 5 sks hulls. Load hole 5 1/2" casing from

bottom to top by spotting cement through tubing, load both 5 1/2" casing and

5 1/2" and 8 5/8" annulus with cement and shut in underpressure.

Plugging Proposal Received by *MJS* Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 PM Day: 11 Month: April Year: 19 90

ACTUAL PLUGGING REPORT Kaiser Francis ordered 350 sks 65/35 poz 8% gel and 5

sks hulls. Pumped cement in with pump truck. Spotted through tubing. 1. 2 3/8"

tubing at 3570' spotted 100 sks cement w/1 1/2 sks hulls. 2. 2 3/8" tubing at 2070'.

Spotted 113 sks and 1/2 sks hulls, cement circ out of 5 1/2" casing. 3. Annulus pressured

to 400 psig. and shut in at 400 psig. Couldn't pump any cement in 5 1/2" casing. Was

d.v. 4. Sq 5 1/2" casing with 15 sks cement. Max pressure 950 psig. Shut in at 950 psig.

Remarks: Cemented by B. J. Titan (If additional description is necessary, use BACK of this form.)

I (did / did not) observe _____ plugging.

INVOICED

DATE 5-3-90

INV. NO. 28036

RECEIVED
APR 25 1990
CONSERVATION DIVISION
Wichita, Kansas

Signed

Marion J. Schmidt
Marion J. Schmidt (TECHNICIAN)