

1-23

66

6 031482

API NUMBER 15-065-03203-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW SE, SEC. 28, T 10 S, R 23 W/E
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241
Operator: Geneva Resources Inc.
Name & Address: 50 California St. Suite 930
San Francisco, CA 94111

Lease Name Diebolt LKC Unit # 15-3
County Graham 126.75
Well Total Depth 3900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 9 5/8 feet 391

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____
Address Hays, Ks.

Company to plug at: Hour: PM Day: 23 Month: Jan Year: 19 91

Plugging proposal received from Gerald

(company name) Geneva (phone) _____

were: 9 5/8 set at 391 w/300 sks cwc. 5 1/2 set at 3899 w/200 sks.

PBTD 3854. Perfs 3713 - 3816. Shots at 1100 Kiowa 1925 anhy. Order tubing
work string. 350 sks 65/35 poz 10% gel 500 lbs. hulls. Halliburton Cement Co.
Wellbrock water truck. Express Well Service rig.

RECEIVED
COMMISSION
2-13-1991
FEB 13 1991

Plugging Proposal Received by Carl
(TECHNICIAN)'S

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00PM Day: 23 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT Ran tubing to 1900 circulated cement laid down tubing
and sq 5 1/2 w/total 310 sks cement. Bld w/500 lbs. hulls mixed in to max psi
150 lbs. Sq 9 5/8 w/40 sks to max psi 500 lbs. Close in psi 150 lbs. Plug
complete.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-22-91
INV. NO. 30809

J. S.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow