

15-065-03199-00-00

10-17

6 031442

API NUMBER 15- 1955

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW NW, SEC. 28, T 10 S, R 23 W/E

3630 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241

Lease Name Diebolt Unit Well # 117

Operator: Geneva Resources Inc.
Name & Address: 50 California Suite 930
San Francisco, California
94111

County Graham 127.23

Well Total Depth 3915 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 239

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number

Address Hays, Ks.

Company to plug at: Hour: AM Day: 17 Month: Oct Year: 19 90

Plugging proposal received from Gerald Riedel

(company name) Geneva (phone)

were: 8 5/8 set at 239 w/170 sks cwc 5 1/2 set at 3914 w/150 sks. Pbsd 3914.

D.V. at 1933 circ w/chem-pac. Order 300 sks 65/35 poz 10% gel 500 lbs. hulls Halliburton Cemen

Sally's water trucks. Express Well Service #758. Ran tubing. Fish at 1560.

Washed over to 1800. Holes in casing. Below Cedar Hills. washover circ. Trace of red sand.

Plugging Proposal Received by Carl (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00 PM Day: 17 Month: Oct. Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 1524 mixed and pumped through tubing

100 sks cement blend. Laid down 800 of tubing mixed and pumped 50 sks of cement blend to circ.

Laid down tubing sq 5 1/2 with total of 200 sks to max psi 600 lbs. Close in psi 500 lbs.

Sq annulus w/100 sks to max psi 300 lbs. Close in psi 200 lbs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
11-8-1990
NOV 8 1990

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-13-90

INV. NO. 29949

lib S

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow