

4-032167

7-30

API Number: 15- - 1954

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NE SE NW /4 SEC. 28, 10, 23 W
3630 feet from S section line
2970 feet from E section line

Operator license# 31638

Lease: Diebolt Unit Well # 11-3

Operator: Manta Petroleum, Inc.

County: Graham 126.91

Address: P.O. Box 4491
Englewood, CO 80155

Well total depth 3905 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 228 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 30 Month: July Year: 1996

Plugging proposal received from: Carl Zimmerman

Company: Manta Petroleum, Inc. Phone: -

Were: Order 375 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
KANSAS CORP COMM
8-9-1996
1996 AUG - 8 12 04

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 11:00 A.M., Day: 30, Month: July, Year: 1996

Actual plugging report: 8 5/8" set at 228' cwc with 150 sxs. 5 1/2" set at 3905' with 150 sxs. Stage collar set at 1926' with Ken-Pac to surface. Squeezed at 1391' and 1406' with cement N.A. Prod. Perfs 3838' - 3860'. PBSD 3813'. Squeezed 5 1/2" with 325 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 400#. Close in P.S.I. 300#. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 250#. Held. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Any plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [] / did not [X] observe the plugging.

Carl Goodrow (agent)

INVOICED
DATE 8-9-96
INV. NO. 46221