

1-23

7/P

6 031480

API NUMBER 15-065-03189-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SE SW, SEC. 28, T 10 S, R 23 W/Ex  
990 feet from S section line

TECHNICIAN'S PLUGGING REPORT

2970 feet from E section line

Operator License # 30241

Lease Name Diebolt LKC Unit Well # 14-2

Operator: Geneva Resources Inc.

County Graham 125.84

Name & Address 50 California Street Suite 930

Well Total Depth 3872 feet

San Francisco, Ca. 94111

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number

Address Hays, Ks.

Company to plug at: Hour: PM Day: 23 Month: Jan Year: 19 91

Plugging proposal received from Gerald

(company name) Geneva (phone)

were: 8 5/8 set at 240 w/175 sks cwc. 5 1/2 set at 3870 w/175 sks. D.V. tool

at 1900 w/425 sks cwc. PBDT 3842. Order 350 sks 65/35 poz 10% gel 500 lbs. hulls.

Halliburton Cement Co. Wellbrock water truckjs. This well had tools pulled out

prior to plugging w/hole open to prod. perms.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:55PM Day: 23 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT Sq 5 1/2 w/340 sks cement blend w/500 bs. hulls

mixed into max psi 1200 lbs. Close in psi 200 lbs. 8 5/8 took 10 sks then

locked up and blew out head. Filed old rathole up w/10 sks slurry. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
2-13-1991  
FEB 13 1991

Remarks: If additional description is necessary, use BACK of this form.

INVOICED

DATE 2-22-91

INV. NO. 30811

J.G.S.

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow