

15-015-400,91-00-00  
2 030557  
11-7-87

R  
102

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- ~~Plugged 1930 or 1931~~

SW, SEC. 13, T 29 S, R 3 ~~XX~~ WE

2310 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # \_\_\_\_\_

Lease Name Knolls Well # old well

Operator: Kansas Corporation Commission

County Butler

Name & Address 202 W. First, Suite 200

Well Total Depth unknown feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size \_\_\_\_\_ feet

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated old well

Plugging Contractor Gresel Corporation License Number 5822

Address Haysville, KS

Company to plug at: Hour: 16:00 Day: 6 Month: 11 Year: 19 87

Plugging proposal received from KCC

(company name) District #2 Office (phone) \_\_\_\_\_

were: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

NOV 23 1987

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Kirkpatrick, Thompson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 16:45 Day: 7 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT Found hole. Set 2' of 3" 8 5/8" conductor casing. Drilled 7 7/8" hole to 90'. Came out of hole, shut down. 11-7-87 Put on 3 1/2" bit, drilled to 170', pulled out of hole. Ran 5 1/2" casing to 62', United Cementing #0880 pumped 290' sxs cement 3% cc down 5 1/2" casing to surface. Shut in, let set. Flow stopped. Filled 5 1/2" casing with 10 sxs common cement, 3% cc.

Remarks: 11-9-87 Checked well, no sign of seepage.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I did / did not observe this plugging.

Signed Alan Thompson  
(TECHNICIAN)

DATE 11-9-87

INV. NO. \_\_\_\_\_