

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

7-22
15-015-40075-00-00

2-050708

FEEFUND

API NUMBER: DRILLED 1916

NE SE NW, SECTION 23 TOWNSHIP 25 RANGE 4E

OPERATOR LICENSE # 100 3630 FEET FROM S SECTION LINE
OPERATOR KANSAS CORPORATION COMMISSION 2790 FEET FROM E SECTION LINE
NAME & 130 SOUTH MARKET #2125
ADDRESS WICHITA, KS 67202

LEASE NAME: HOPKINS #1
COUNTY: BUTLER
WELL TOTAL DEPTH: 700'
PIPE:
SURFACE CASING: 10" UNKNOWN

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: CONTROL #970181-001

PLUGGING CONTRACTOR: HOGOBOOM OILFIELD TRUCKING

ADDRESS: 767 OILHILL ROAD, EL DORADO, KS 67042 LICENSE: 7971

COMPANY TO PLUG AT: HOUR: 13:00 DAY: 18 MONTH: 7 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT II

COMPANY NAME: UNITED CEMENTING PHONE: (316) 321-4680

WERE: DIG OUT WELLHEAD AND CELLAR, DIG PIT. RIG UP PULLING UNIT. RUN TUBING AND BIT AS FAR AS POSSIBLE. DRILL TO 700'. CIRCULATE CEMENT TO SURFACE. PULL TUBING AND BIT OUT OF HOLE AND TOP OFF WITH CEMENT. CUT OFF CASING. CLOSE PIT. REMEDIATE SURFACE DAMAGE.

PLUGGING PROPOSAL RECEIVED BY: LOREN JACK

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 11:00 DAY: 22 MONTH: 7 YEAR: 1997

ACTUAL PLUGGING REPORT: DUG OUT WELLHEAD AND CELLAR. DUG PIT. RIGGED UP PULLING UNIT, RAN TUBING AND BIT TO 320'. DRILLED TO 406', NO CIRCULATION. PULLED TUBING AND BIT OUT OF HOLE. RAN TUBING BACK TO 120'. WASHED DOWN TO 310'. SPOTTED 100 SACKS OF CEMENT. PULLED TUBING OUT OF HOLE. LET SET. RAN TUBING TO 93' AND SPOTTED 100 SACKS OF CEMENT. PULLED TUBING OUT OF HOLE. LET SET. RAN TUBING TO 43' AND CIRCULATED CEMENT TO SURFACE. PULLED TUBING OUT OF HOLE. CUT OFF CASING. CLOSED PIT. REMEDIATED SURFACE DAMAGE.

REMARKS 60/40 POZ 2% GEL 250 SACKS CEMENT UNITED #4169 & #4156

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 17 1997

CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

JERRY CLARK

FORM CP-2/3
REV. 3/90