

6 070262

API NUMBER 15-065-22,103 **R**

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE-SW-NE, SEC. 18, T 10 S, R 24 W/E

3630 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5190

Lease Name HOBBS Well # 1

Operator: SABRE EXPLORATION, INC.

County GRAHAM 130.00

Name & Address 310 W. CENTRAL, SUIT # 214

Well Total Depth 4000 feet

WICHITA, KANSAS

Conductor Pipe: Size 0 feet

67202

Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor REPUBLIC DRILLING, INC. License Number 9943

Address 310 West CENTRAL, # 214 WICHITA, KANSAS 67202

Company to plug at: Hour: 1:00 AM Day: 19th Month: NOV Year: 19 84

Plugging proposal received from LARRY BELDING

(company name) REPUBLIC DRILLING, INC. (phone) 316-264-2635

were: 8 5/8" - 262' S.P. CUC #185 5% 60' / 40' FORMIX GEL - CA-CL - (734 SUN.)

ORDER 210 5% 50' / 50' FORMIX GEL - CA-CL - 1 5% 70' CELE AND 8 5/8" PLUG

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

NO CIRCULATION PROBLEMS, K.C. Well - EV. 2463. ANN. 2099.

MUD VISCOSITY 46 - Weight 9.5.

Plugging Proposal Received by Marcus Schmidt
RBIC (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:10 AM Day: 19th Month: NOV Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 210 5% 50' / 50' FORMIX GEL - CA-CL - 1 5% 70' CELE + 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS

1st PLUG @ 2110 FT #30 SK CNT, 2nd PLUG @ 1230 FT #100 CNT + 1 SK 70' CELE,

3rd PLUG @ 360 FT #60 SK CNT, 4th PLUG SOLID BRIDGE HULLS - PLUG @ 40 FT #10 SK CNT

10" IN RAT HOLE (CIRCULATE) (CEMENTED BY SUN CEMENTING)

RAT HOLE - RE-PLUGGED ON 11-28-84 BY SWD.

Remarks: (If additional description is necessary, use BACK of this report)

RECEIVED
STATE CORPORATION COMMISSION
12-3-1984
DEC 03 1984

I (did / did not) observe this plugging.

DATE 12-13-84

INV. NO. 5977

JAN 14 1985

Signed Marcus Schmidt
RBIC (TECHNICIAN)