

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-065-21521-00-01  
API NUMBER 15-065-21,521

LEASE NAME Denio 'P'

WELL NUMBER 5

Ft. from S Section Line

Ft. from E Section Line

SEC. 5 TWP. 10 RGE. 24W (E) or (W)

COUNTY Graham

Date Well Completed

Plugging Commenced 9-13-95

Plugging Completed 9-18-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

Suite 100 125 N. Market  
ADDRESS Wichita, Ks. 67202

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4130'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 209'   | none       |
|           |         |      |    | 4-1/2" | 4128'  | 1326'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Plugged off bottom with sand to 3806' and 4 sacks cement. Shot pipe at 2230' and 1339'. Pulled pipe to 2250'. Pumped 80 sacks cement with 300# hulls. Pulled to 150' and circulated cement to surface with 40 sacks cement (60/40 10% gel) and 100# hulls. Hole stayed full. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

STATE OF Kansas COUNTY OF Rice, ss. \_\_\_\_\_

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have read the facts statements, and matters herein contained and the log of the above-described well and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 10th day of October, 1995

Gene Herzberg  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
10-13-1995  
OCT 13 1995  
CONSERVATION DIVISION  
Wichita, Kansas

USE ONLY ONE SIDE OF EACH FORM



Form CP-4  
Revised 05-88