

15-065-02114-00-00

Give All Information Completely
Make Required Affidavit

WELL PLUGGING RECORD

Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County County. Sec. 5 Twp. 10S Rge. 24W (N) (W)

Location as "NE/CNW%SW%" or footage from lines ~~G SW NW~~ C NW SW

Lease Owner Imperial Oil Company

Lease Name Dreiling "C" Well No. 2

Office Address 780 Fourth National Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7/28/62 19

Application for plugging filed 7/28/62 19

Application for plugging approved 7/28/62 19

Plugging commenced 7/28/62 19

Plugging completed 7/28/62 19

Reason for abandonment of well or producing formation

No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4090 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing	8-5/8"	at 183'		not pulled		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug at 550' with 20 sacks

Set second plug at 175' with 20 sacks

Set top plug at 40' with 10 sacks

RECEIVED
STATE CORPORATION COMMISSION
8-13-1962
AUG 1 1962
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address Box 97, WaKeeney, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

John Lehman

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

John Lehman

780 Fourth Natl. Bldg., Wichita, Kansas

(Address)

9th day of August, 1962

Bette J. Silcott

Notary Public.

My commission expires July 5, 1966



DRILLER'S LOG

Imperial Oil Company
780 Fourth National Building
Wichita, Kansas

DREILING "C" NO. 2
~~C SW NW~~ Sec. 5-10S-24W
~~C NW SW~~
Graham County, Kansas

Total Depth: 4090'

Elevation: 2526 K.B.
Production: Dry

Commenced: 7/19/62 Completed: 7/28/62

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" surface pipe at 183' with 150 sacks cement.

Figures indicate bottom of formations:

TOPS

Surface Clay and Sand	183'	Heebner	3816 (-1290)
Shale	1510'	Toronto	3840 (-1314)
Shale and Shells	1740'	Lansing	3850 (-1324)
Dakota Sand	1930'	Base Kansas City	4085 (-1559)
Shale and Red Bed	2170'	Rotary Total Depth	4090 (-1564)
Anhydrite	2208'		
Shale and Shells	2350'		
Lime and Shale	3885'		
Lime	4090'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Raymond L. Bacon
Raymond L. Bacon

Subscribed and sworn to before me this 2nd day of August, 1962.

My Commission Expires: July 5, 1966

RECEIVED
STATE CORPORATION COMMISSION
8-13-1962
AUG 13 1962

Bette J. Silcott
Bette J. Silcott, Notary Public

CONSERVATION DIVISION
Wichita, Kansas