

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

WELL NUMBER 15-065-20,829

LEASE NAME Gano "P"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER # 2 SWD

3630' Ft. from S Section Line

990' Ft. from E Section Line

SEC. 5 TWP. 10 SRGE. 24 W(E) or (W)

COUNTY Graham

Date Well Completed 5-76

Plugging Commenced 12-16-91

Plugging Completed 12-16-91

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well SWD Docket # D-21,799

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-16-91 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Disposal Formation Cedar Hills Depth to Top 1715 Bottom 1805 T.D. 4100'  
Producing Formation \_\_\_\_\_ PBTB 1876'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	207'	0
				4 1/2"	4095'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pulled tubing & Packer. Ran wireline thru Cedar Hills perfs to verify that perfs were clear. Perforated 4 1/2" csg at 1390'. Pumped down 4 1/2" csg: 110 sxs 65/35 poz. and 90 sxs same and 400# hulls. Max PSI 900#. Shut in at 600#. Pumped down 8 5/8" csg: 150 sxs 65/35 pozmix and 10% gel and 100# hulls. Max PSI = 400#. Shut in (If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. \_\_\_\_\_

Address P.O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ritchie Exploration, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market, Suite 1000  
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 9 day of January, 19 92

[Signature]  
Notary Public

My Commission Expires: LISA THIMMESCH  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 8-24-95

at 200#. Plugging complete at 10:15 AM 12-16-91. Witnessed and approved  
by Carl Goodrow with the KCC.