

15-065-22692-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,692

LEASE NAME Anton Herman

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 3

3,630 Ft. from S Section Line

3,960 Ft. from E Section Line

LEASE OPERATOR Staab Energy & Leasing

SEC. 9 TWP. 10 RGE. 24 (X) or (W)

ADDRESS 2514 Haney Drive, Hays, KS. 67601

COUNTY Graham

PHONE#(913) 628-1326 OPERATORS LICENSE NO. 03655

Date Well Completed 10-1-92

Character of Well D & A

Plugging Commenced 10-1-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-2-92

The plugging proposal was approved on 10-1-92 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,090'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	221'	Cmtd. w/165 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot 25 sax cement @2,180' thru drill pipe. Push bridge plug to 1,290', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 275', spot 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Staab Energy & Leasing

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of ~~Operator~~ contractor) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec. - Treas.


(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 12th day of October, 1992

Lute Phillips
Notary Public

RECEIVED
10-14-1992
OCT 14 1992

My Commission Expires:



CONSERVATION DIVISION
Wichita, Kansas
CP-4
05-88



Shields


15-065-22692-00-00

Russell, Kansas

WELL LOG

Operator: Staab Energy & Leasing
 Well: Anton Herman #3
 Commenced: September 25, 1992
 Completed: October 2, 1992
 Contractor: Shields Drilling Co.

Well Description: N/2 S/2 NW
 Sec. 9-10S-24W
 Graham Co., KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	221'	Cmtd. w/165 sax

Elevation: 2,516' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Shale & sand	55'
Sand	224'
Shale & sand	2,163'
Anhydrite	2,198'
Shale & sand	2,205'
Shale	2,585'
Shale & lime	3,976'
Lime	4,090' RTD

Notes

RECEIVED
 STATE CORPORATION COMMISSION
 10-14-1992
 OCT 14 1992
 CONSERVATION DIVISION
 Wichita, Kansas