


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 10 Twp. 10 Rge. 24 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner C-G Drilling Co. & Houston Petroleum Co.
Lease Name Anderson "A" #3 Well No.
Office Address 107 Rule Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 17 19 61
Application for plugging filed December 17 19 61
Application for plugging approved December 17 19 61
Plugging commenced December 17 19 61
Plugging completed December 17 19 61
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4025 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	192.11'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 550'. Set plug. Put in 20 sacks cement. Filled to 180'. Set plug. Put in 1-1/2 sacks hulls and 15 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1961 12-28-61

CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) G. F. Galloway
(Address) 107 Rule Building

SUBSCRIBED AND SWORN to before me this 20th day of December, 19 61

My commission expires May 20, 1963 Vicky Jacobs Notary Public.



15-065-01022-0000

WELL LOG

OPERATOR C-G Drilling Co. & Houston Petroleum Co. **SEC.** 10-10-24
WELL NAME Anderson "A" #3 **LOC.** SE NW NW
TOTAL DEPTH 4025' **COUNTY** Graham
COMM. December 6, 1961 **COMP.** December 17, 1961 **STATE** Kansas
RIG NO. 1 **ELEVATION** 2456' K.B.
CASING: Ran 192.11' (10 jts.) 8-5/8" OD Surface Casing. **PRODUCTION:** D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	2081	Shale & Sand		
2081	2120	Anhydrite		
2120	2395	Shell & Shale		
2395	2870	Shale & Lime	00 - 2500	
2870	3575	Lime & Shale	00 - 2750	
3575	3710	Lime	00 - 3000	
3710	3795	Lime & Shale	00 - 3250	
3795	3873	Lime	00 - 3500	
3873	3925	Lime & Shale	00 - 3750	DST 3888-3925'
3925	3945	Lime		DST 3926-3945'
3945	3965	Lime & Shale		DST 3940-3965'
3965	3995	Lime		DST 3960-3990'
3995	4025	Lime & Shale		

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 9 1962
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By

G. F. Galloway

AND SWORN TO, BEFORE ME, THIS 20th day of December, 1961.

My commission expires:

1963

Vicky Jacobs - Notary Public

