

15-065-2030-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
100 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER Unkown

LEASE NAME D. RUSH "B"

WELL NUMBER 3

990 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 17 TWP. 10S RGE. 24W (E) or (W)

COUNTY GRAHAM

Date Well Completed 4/2/68

Plugging Commenced 2/22/90

Plugging Completed 2/23/90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR CRUMP PETROLEUM CORP.

ADDRESS P.O. BOX 50820, Midland, Texas 79701

PHONE # 015 ) 687-2008 OPERATORS LICENSE NO. 03135

Character of Well OIL WELL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/23/90 (date)

by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed? No If not, Is well log attached? YES

Producing Formation LANSING- K.C. Depth to Top 3724 Bottom 3928 T.D. 3950

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LANSING-K.C.	Depleted oil	3724	3928	8-5/8"	175	NONE
				4-1/2"	3989	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Pulled & parted tbg. from 1830. Made 2 attempts to pull remaining tbg. Was badly corroded. Could not recover. Ran tbg to 1829'. Ppd 200 sxs 65-35 Poz. + 8% gel & 350# hulls. Cmt Circ. Pulled tbg. & ppd 20 sxs cmt. + 100# hulls. S.I. Press. 1000#. Sqzd. Annulus w/150 SXS S.I. 500#  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor MURFIN DRILLING CO. License No. 6033


Address P.O. Box 130, Hill City, Kansas 67642

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CRUMP PETROLEUM CORP.

STATE OF TEXAS COUNTY OF TARRANT, ss.

ROBERT D. BOCELLI, AGENT (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert D. Bocelli  
(Address) 2115 Melissa St. Arlington, TX 76010



3-12-1990  
SUBSCRIBED AND SWORN TO before me this 26<sup>th</sup> day of February, 19 90.

Deane Snow  
Notary Public

Commission Expires: 6-9-90