

15-065-20029-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market - Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-20,029

LEASE NAME D. Rush 'B'

WELL NUMBER 1

330 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 17 TWP. 10 RGE. 24 (E) or (W)

COUNTY Graham County, KS

Date Well Completed 4/12/67

Plugging Commenced 10/26/98

Plugging Completed 10/26/98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS P. O. Box 70 Hays, KS 67601

PHONE# (785) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/26/98 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? ? If not, Is well log attached? sent w/CP-1

Producing Formation Lansing-Kansas City Depth to Top 3745 Bottom 3971 T.D. 4000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	187	0
				4 1/2	4000	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Perforate @ 1225' w/two holes. Pump 250 sx cement (60/40 poz, 10% gel, 500# hulls) down casing. Pressure annulus (8 5/8 - 4 1/2") to 500#, no entry. Pump 100 sx cement (60/40 poz, 10% gel) down casing, shut in 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. NA

Address P. O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_


STATE OF Kansas COUNTY OF Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 19 98



My Commission Expires: 10-18-2000

Notary Public

RECEIVED  
KANSAS CORP COM.  
NOV -5 P 1:43  
15-1998