


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 17 Twp. 10 Rge. (E) 24 (W)

Location as "NE/CNW/SW" or footage from lines C SW 1/4 SE 1/4

Lease Owner Imperial Oil Company

Lease Name Rush Well No. 1

Office Address 780 Fourth National Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 30, 1961 19

Application for plugging filed June 30, 1961 19

Application for plugging approved June 30, 1961 19

Plugging commenced June 30, 1961 19

Plugging completed June 30, 1961 19

Reason for abandonment of well or producing formation

No commercial quantities of oil found.

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation Lansing KC Depth to top 3766 Bottom 4003 Total Depth of Well 4010 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface casing				8-5/8"	193'	Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set first plug at 550' with 20 sacks;  
second plug at 185' with 15 sacks;  
top plug at 40' with 10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION  
6-2-1961  
AUG 2 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address 780 Fourth National Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

William A. Sladek

(employee of owner) ~~XXXXXXXXXXXX~~

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William A. Sladek


780 Fourth National Bldg., Wichita, Ks.

(Address)

SUBSCRIBED AND SWORN to before me this 1st day of August, 19 61

Bette J. Behymer  
Bette J. Behymer Notary Public.

My commission expires July 27, 1964



DRILLER'S LOG

Imperial Oil Company  
780 Fourth National Building  
Wichita 2, Kansas

Rush No. 1  
C SW SE Sec. 17-10-24W  
Graham County, Kansas

Total depth: 4010'

Elevation: 2437' K.B.  
Production: Dry

Commenced: 6-20-61 Completed: 6-30-61

Contractor: Imperial Oil of Kansas, Inc.  
Wichita, Kansas

Casing Record: Set 8-5/8" surface pipe at 191' with 150 sacks of cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	(Sample)
Surface Clay, Rock & Sand	191'	Heebner	3728 (-1291)
Sand, Shells & Shale	950'	Toronto	3751 (-1314)
Sand & Shale	1565'	Lansing	3766 (-1329)
Shale, Shells, Dakota Sand	1820'	B/Kansas City	4003 (-1566)
Shale - Red Bed	2065'	Total Depth	4010 (-1573)
Anhydrite	2105'		
Shells & Shale	2260'		
Shale & Lime	2510'		
Lime & Shale	3755'		
Lime	4010'		
Rotary Total Depth	4010'		

We hereby certify this to be a correct and accurate log of the above described test well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Raymond L. Bacon  
Raymond L. Bacon

Subscribed and sworn to before me this 7th day of July, 1971.

My commission expires:

July 27, 1964

**RECEIVED**  
STATE CORPORATION COMMISSION  
8-2-1961  
AUG 2 1961

Bette J. Behymer  
Bette J. Behymer, Notary Public

CONSERVATION DIVISION  
Wichita, Kansas