

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
6-5-1964
JUN 5 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bill Hicks of Southwest Csg. Pulling Co. has this date requested permission to plug the following described well:
Imperial Oil of Kansas
Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil of Kansas.

Complete Address: Box # 97, Wakeeney, Kansas.

Lease Name: Dreiling Well No. C-1

Location: CSW-SW Sec. 5 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4070 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hicks was instructed to plug the well as follows:

219'--8 5/8" Surface pipe, cement circulated with 175 Sx.
4039'--4 1/2" production casing cemented with 150 Sx. Well
plugged back to 4043'. Top perforations 3875' to 3879'.

Sand well back to 3865' and set 3 Sx. cement with dump bailer.
Pull 4 1/2" to 600' and circulate heavy gel mud. Pull 4 1/2" to 540'
and displace 20 Sx. cement. Pull 4 1/2" to 190' and displace 20
Sx. cement thru 4 1/2". Pull 4 1/2", set bridge @ 35' and 10 Sx.
cement to bottom of cellar.

Very truly yours,

W. D. Nichols