



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

1-4-1973  
JAN 4 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this

date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Don Pratt,

Complete Address: Box #370, Hays, Kansas.

Lease Name: Elmer Gano Well No. C-1

Location: 440' FSL & 440' FWL-NE/4 Sec. 5 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4070' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

221'--8 5/8" Surface, cement circulated with 165 Sx.  
Top of Dakota section @ 800'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

*M. G. Nichols*

Conservation Division Agent