



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION  
8-13-1973  
AUG 13 1973  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Niernberger of Murfin Drilling Company has this  
date requested permission to plug the following described well:Mr. Niernberger guarantees payment of the plugging fee.Operator's full Name: Don E. Pratt,Complete Address: Box #370, Hays, Kansas.Lease Name: Herman Well No. 1Location: SE-SE-NW Sec. 9 Twp. 10 Rge. (E)(W) 24County: Graham Total Depth 4052' Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Niernberger was instructed to plug the well as follows:196'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 925'.Circulate hole with heavy mud. Pull DP to 1150' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with  $\frac{1}{2}$  sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent