

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
6-23-1971  
JUN 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Russell Sullivan of Russ Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company.

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Manz Well No. 11

Location: SE-SW-SE Sec. 12 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 4016' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.

4013'--5 1/2" Production casing cemented on bottom with 100 Sx. Top perforations @ 3980'.

Sand well back to 3900' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement, staged.

Very truly yours,

*H. L. Nichols*  
Conservation Division Agent